

Estimate for - Repairing, painting and repairing false ceiling of Department Lab at animal Nutrition department at Bidgachia including Terfing work of A.C. sheds under WBURFS Vol. 37

Page Sten	SL No	Description of Item	Quantity	Unit	Rate Rs	Amount Rs.
$\frac{8}{10}$	1	stripping off worn out plaster & raking out joint of walls ceiling etc	40.00	m ²	19.00	760.00
$\frac{151}{8}$	2	15mm thick plaster with mix (1:4) - - -	50.00	m ²	176.00	8800.00
$\frac{14}{7}$	3	ordinary cement concrete with mix (1:1½:3)	0.60	m ³	6603.00	3962.00
$\frac{120}{101}$	4	Solid type door of dular decorative both side equally timber frame consisting of top & bottom rail side styles etc. in order to make the door solid core and internal lipping with teak, mahagoni etc wood approved decorative veneer using phynol formaldehyde or glue etc 35mm thick sutter single leaf	2.00	m ²	3142.00	6284.00
$\frac{99}{66}$	5	Anodised Aluminium Aldrop sliding bolt	2	NO	347.00	694.00
$\frac{161}{5}$	6	Rendering surface of wall with cement based putty	50.00	m ²	122.00	6100.00
$\frac{158}{15}$	7	Applying exterior grade primer - - -	220.00	m ²	34.04	7489.00 45678.00
$\frac{163}{9}$	8	Applying Acrylic emulsion paints of approved make including smoothing surface two coats	220.00	m ²	76.00	16720.00
$\frac{162}{7}$	9	Priming on timber/steel surface - - -	30.00	m ²	31.00	930.00
$\frac{162}{8}$	10	Painting with best quality synthetic enamel paints of approved make & brand including smoothing surface two coats	50.00	m ²	86.00	4300.00
$\frac{6}{7}$	11	supplying fitting fixing (bi-cock) stop cock Chromium plated Esseco 15mm dia	3	m ²	689.00	2067.00
—	12	Supplying and laying standard course bituminous water proofing terfelt as per specification including necessary preparatory work such as smoothing surface removing old layer, applying bitumen Type-3 grades conforming to IS. 3240/10m ² etc all complete with local best quality terfelt on A.C. roof	110.00	m ²	175.00	19250.00

Page No	SL No	Description of Item	Quantity	Unit	Rate Rs	Amount Rs.
240 21 g (ii)	13	Supplying fitting fixing Eco brandy moisture resistance False ceiling (ii) 12.5mm thick Sema edge gypsum plastered board including all cost (for repair of old false ceiling)	26.00	M ²	464	12064.00
173 21(A) (ii)	14	(a) Supplying fitting fixing UPVC pipe A type and fitting complete including clamp cost etc for rainwater pipe 110mm dia	22.00	m	291.00	6402.00
	(b)	UPVC Plain Tee 110mm dia	3	NO	117.00	351.00
	(c)	UPVC bend 110mm dia.	3	NO	162	468.00
						<u>88721.00</u>

24/2/17
SUB-ASSISTANT ENGINEER
West Bengal University of
Animal and Fishery Sciences

24.02.17
(Er. S. Roy)
B.C.E., M.B.A.
Consultant Engineer
W. B. University of Animal & Fishery Sciences
68, K. B. Sarani, Kolkata-700037

Page No	SL No	Description of Item	Quantity	Unit	Rate Rs	Amount Rs.
240 21 g (ii)	13	Supplying fitting fixing Eco brandy moisture resistance False ceiling (ii) 12.5mm thick Semi edge gypsum plastered board including all cost (for repair of old false ceiling)	26.00	M ²	464	12064.00
173 21(A) (ii)	14	(a) Supplying fitting fixing UPVC pipe A type and fitting complete in chd. clamp cost etc for rainwater pipe 110mm dia	22.00	m	291.00	6402.00
	(b)	UPVC Plain Tee 110mm dia	3	NO	117.00	351.00
	(c)	UPVC bend 110mm dia.	3	NO	162	468.00
						<u>88721.00</u>

24/2/17
SUB-ASSISTANT ENGINEER
West Bengal University of
Animal and Fishery Sciences

24.02.17
(Er. S. Roy)
B.C.E., M.B.A.
Consultant Engineer
W. B. University of Animal & Fishery Sciences
68, K. B. Sarani, Kolkata-700037