

Estimate: Repair and renovation of Farmer's Hostel, (A) aluminium sliding windows and false ceiling at Photo Gallery, (B) floor tiles at Room No. D₁ & D₆ aluminium partition walls, cubical at Room No. D₃ at 37, K. B. Sarani, Kolkata under WBUAFS.

| Page No. | Sl. No | Name of the work | Quantity | Rate(Rs.) | Unit | Amount(Rs.) |
|------------------|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|----------------|-------------|
| P-126 It 99 | 1. | Providing false ceiling with power coated exposed GI grid suspension system consisting of main..... 3600 mm long cross tee 1,200 mm/600mm long and all angles, the wall angle shall be fixed on PVC dask.....GI wire from ceiling etc. a) False ceiling with 6 mm thick fibre cement designer board E-grid. Photo Gallery- | 20.00 | 794.00 | M ² | 15880.00 |
| | 2. | Aluminium sliding windows two track or three track of aluminium alloy..... in colour including all best glazing clip.....fixed glazy all complete. | 14.00 | 3150.00 | M ² | 44100.00 |
| P-52 It-32 | 3. | Supply fitting fixing 1 st quality ceramic tiles in wall and floor to match with the existingwith colour pigment if necessary (A) in floor, with sand and cement mortar(4:1) 20 mm thick and 2 mm thick cement slung. <i>area above = 0.09 m²</i> | 65.00 | 1040.00 | M ² | 67600.00 |
| | 4. | Chipping concrete surface etc. as directed | 90.00 | 20.00 | M ² | 9020.00 |
| P-11 It-5 | 5. | Ordinary cement concrete(1:2:4) mixed with pakur variety stone chips 20 mm <i>dia. size</i> | 0.60 | 6064.00 | M ³ | 3638.00 |
| P-151 It-2(I) | 6. | 15 mm thick plaster to wall etc. with mixed with (1:4) | 105.00 | 176.00 | M ² | 18480.00 |
| P-155 It-1 | 7. | Scraping of moss, blisters etc. thoroughly from surface wall etc. | 75.00 | 7.00 | M ² | 525.00 |
| P-157 It-14 | 8. | Applying interior grade acrylic primer of approved quality and brand of plastered surface water base interior grade acrylic primer. | 180.00 | 33.33 | M ² | 5999.00 |

| | | | | | | |
|------------------------------------------------------------|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|----------------|-------------------------|
| P-157 It10 | 9. | Acrylic distemper to interior wall ceiling with including clinic and smothering surface two course | 180.00 | 76.00 | M ² | 13680.00 |
| P-162 It-7 | 10. | Priming one coate with oil bound primer approved quality one coate on still surface. | 35.00 | 31.00 | M ² | 1085.00 |
| P-162 It-8 | 11. | Painting with best quality synthetic wall bound paints high glose(two course). | 35.00 | 89.00 | M ² | 3115.00 |
| | 12. | Aluminium partition wall with 1/3 rd glass and 2/3 rd SEP Board with approved aluminium section manufactured by Hindal/ADEMAL or equivalent section including all costs of materials, glassing clip, gasket, all complete. (a) Partition wall 2/3 rd SEP Board and 1/3 rd glass at Room No. D ₃ (b) Aluminium single leaf swing door with 2/3 rd SEP Board and 1/3 rd glass and maruty lock 100 mm = 3x2.00x1.00=6.00 M ² | 28.00 | 3050.00 | M ² | 85400.00 |
| P-204 It-13(c) | 13. | Acrylic handle 125 mm dia supplying fitting complete at Room No. D ₃ , 3x2-6 nos. | 6.00 | 228.00 | NO | 1368.00 |
| P-204 It13 | 14. | Supplying fitting fixing aluminium coated body hydraulic door close as per ISI at Room No. D ₃ | 3.00 | 757.00 | NO | 2271.00 |
| Total: | | | | | | <u>291061.00</u> |
| (Rupees two lac ninety one thousand sixty one only) | | | | | | |

Ram
SUB-ASSISTANT ENGINEER
West Bengal University of
Animal and Fishery Sciences

M. J. Sarani
30.8.17
Consultant Engineer
W. B. University of Animal & Fishery Sciences
68, K. B. Sarani, Kolkata-700037