

Estimate for - Construction of a Tin shed above ground floor roof of existing mess at Chakaria, under fishery science Under WBUAFS.

Page NO	Sl NO	Description of Item	Quantity	Unit	Rate Rs	Amount Rs
P-7 91-3	1	Dismant R.C. floor roof Col etc including removing rubbish lead 75 m.	1.5 1'20	M	1975'00	2370'00
P-74 91-2AU	2	M.S. structural work with hollow section (7A7A) make square or rectangular shape connected to one another with bracket gasket cleat as per design drawing as directed complete including cutting to rectangular shape & size fabrication, metal or Arc welding conforming to IS. using electrode of approved brand. The rate inclusive the cost of all materials labour charges span 8-80 m including cost of one coat primer and two coats of approved paints	2'50	Mt	6800'00	17000'00
P-14 91-5	3	Ordinary cement concrete with mix (1:2:4) with 20mm size stone chips	1'00	M <sup>3</sup>	6160'00	6160'00
P-232 91-8(B)	4	supplying fitting fixing Zn-Al alloy coated steel sheet work having of approved name fitted and fixed with 10mm dia J or L hook bolt, limped and bitumen washer and putty complete with 150mm end lapping and one corrugation minimum side lapping & in roof 0.900mm thick	340'00	M <sup>2</sup>	905'00	3077'00
P-65 91-10-30	5	Galvanised iron sheet riging and fixed with 6mm dia J or L hook-bolt and putty with 150mm and 300mm minimum lapping with 0.6300mm thick sheet	27'00	M	430'00	11610'00
<p>(Rupees four lac ninety seven thousand eight hundred forty five only)</p> <p>Rs 497845'00</p>						

SUB-ASSISTANT ENGINEER  
West Bengal University of  
Animal and Fishery Sciences

30817