

Estimate for - Supplying and laying interlocking designer paver block on the approach road in front of Vivek Bhaban at B.B.K. Sarani Krf 37 under WBUAFL

Page NO	Sl NO	Description of Item	Quantity	UNIT	RATE
P-57 91-40 (b)	1	supplying & laying interlocking designer paver block of any shed and approved quality as per IS 1237 laid in pattern as directed in pavement including necessary underlay complete in all respect with all labour & materials b) 40mm thick block over 150mm medium sand bed including cost of sand. i) colour decorative in front of Vivek Bhaban $23.00 \times 3.80 = 87.40$	88.00	M <sup>2</sup>	
P-29 91-21	2	1st class brick work in cement mortar (1:6) in front of Vivek Bhaban $2 \times 23.00 \times 0.25 \times 0.16 = 1.80m^3$	2.00	M <sup>3</sup>	
P-151 91-2	3	15mm thick plaster with cement mortar (1:4)	20.00	M <sup>2</sup>	
	4	Heat cement panning - - - - -	20.00	M <sup>2</sup>	

Roang  
6/7/17

SUB-ASSISTANT ENGINEER  
West Bengal University of  
Animal and Fishery Sciences

06.07.17

(Er. S. Roy)  
B.C.E., M.B.A.  
Consultant Engineer  
W. B. University of Animal & Fishery Sciences  
68, K. B. Sarani, Kolkata-700037

A  
72031