

Estimate for - Repair of ~~existing~~ ^{existing} and plumbing work and removal of Aluminium partition work and allied work at inside of Vivek Bhaban at 88 K.B. Sarani Kol-37 Under W.B. DAFI

Page No	Sl No	Description of Item	Quantity	UNIT	RATE	AMOUNT
P-8 97-10	1	Stripping off worn out plaster and raking out joints of walls ceiling etc upto any light removing Spoil load - 75 m ² .	80.00	m ²		
P-151 97-1	2	15 mm thick plaster with cement mortar (1:4)	90.00	m ²		
P-161 97-5	3	Rendering surface of walls and ceiling with white based cement based wall putty of approved make	85.00	m ²		
P-151 97-15	4	Applying exterior grade Aerilic primer of approved make and brand one coat	140.00	m ²		
P-157 97-12	5	Applying Aerilic Distemper to interior wall ceiling including cleaning & smoothening surface Two coats	140.00	m ²		
P-2 97-1(B)	6	supplying fitting fixing GI pipe & ATA make with all necessary fittings in concealed work 15mm dia	15.00	m		
P-5 97-7	7	supplying fitting fixing bib cock stopcock chromium plated Esseo or similar	5	NO		
P-31 97-2(11)	8	supplying fitting and fixing white vitreous china best quality wash basin with ci bracket c.p. wash fittings 82mm dia, one approved quality brass c.p. collar cock 15mm dia ep cam with rubber plug of 30mm dia approved quality pvc wash pipe with ep nut 32mm dia 900mm long approved quality pvc connection pipe with heavy ep nut including mending good all damages and painting the bracket two coats				1 NO
P-52 97-30 B	9	Supplying fitting & fixing 1st quality ceramic tiles in walls to match with the existing work finishing the joint with white cement & colour pigment including backing with sand cement mortar (2:1) mix 15mm thick etc all complete area above 0.09 m ² other than colour decorative including white	11.00	m ²		

Sl. No.	Description of Item	Quantity	Unit
10	Removing and keeping of existing Aluminium glass partition wall and wooden partition wall from examination hall of Vivek Bhawan and		
	Keeping them in position as directed lead 75m including mending good the damages	130'00	sq. m
11	Repairing of damaged false ceiling with replacement of old member ceiling etc including painting the same complete	12'00	sq. m

Roan
6/7/17

SUB-ASSISTANT ENGINEER
West Bengal University of
Animal and Fishery Sciences

S. Roy 06

(Er. S. Roy)
B.C.E., M.B.A.
Consultant Engineer
W. B. University of Animal & Fishery Sciences
68, K. B. Sarani, Kolkata-700037